MIGNON MINDS LLP
42 & 43 Shop No. A6,
Praneeth Pranav Blooms,
Bowrampet, Hyderabad - 500043.

Date: 03/01/2026

To,
MR. KRANTHI,
SHAMSHABAD, HYDERABAD.

Dear Sir,

Sub: Quotation for Waterproofing Works – Ground floor area, Corridors, Staircase & Terrace.

With reference to your enquiry and our site inspection on the above subject, we are pleased to submit our competitive quotation for the proposed waterproofing works using ***Dr. Leakage*** products, for your kind perusal and necessary action.

S No	Description	Units Sq. Ft	Price / Sq. Ft	Amount
1	Ground Floor Area using Dr. Leakage Products	300	₹25.00	₹7,500.00
2	Corridors and Staircase using Dr. Leakage Products	LUMPSUM	₹70,000.00	₹70,000.00
	Terrace Waterproofing using Dr. Leakage Products with 10 years warranty	900	₹70.00	₹63,000.00
			TOTAL	₹140,500.00
			GST 18%	₹25,290.00
			Grand Total	**₹165,790.00**

Bank Account Details:		Payment Terms:
Bank Name	**Kotak Mahindra Bank**	**50% after commencement of work.**
Account Name	**Mignon Minds LLP**	**40% before completion of work.**
Account Number	**9885252076**	**10% after completion of work.**
Account type	**Current**	Price validity lasts for 30 days from the date of quotation
IFSC CODE	**KKBK0007475**	
Branch name	**KPHB (PRATIBA VIDYANIKETAN)**	**Tax No.**
UPI ID	**mignon.llp82@kotak**	36ACDFM6416B1ZK

The application procedures along with the products used are mentioned in detail below.

Ground Floor Area

- Thorough cleaning of the existing surface to remove dust, debris, and loose particles.
- Application of VELOX 2K / One coat of INVISI SHIELD.
- Filling and sealing of side joints and gaps using SBR-based polymer-modified mortar.

First Floor & Second Floor *(Only Corridors and Staircase)*

- Checking and verification of existing slope for proper water drainage.
- Removal of existing granite slabs and re-laying with corrected slope to ensure smooth water flow.
- Waterproofing treatment to slab joints, side joints, and granite gaps.
- Application of 2-feet height SBR-based polymer coating on adjoining walls.
- Painting of SBR-coated wall areas with suitable exterior-grade paint.
- Provision of additional drain outlets, wherever technically feasible and required.

Terrace Waterproofing – 10 years Warranty

- Surface preparation including necessary masonry repairs and crack rectification.
- Jet cleaning using pressure washer at areas to be coated
- Nano-filling the terrace floor with water repellent chemical, penetration up-to 50mm max
- Line Grooving on potential cracks and Crack filling by acrylic polymer – based cement paste
- Priming the surface with cementitious coat (Acrylic Polymer + Cement) DFT – 0.6 to 0.8mm
- Enclosing the Geo-fabric with cementitious coat (Acrylic Polymer + Cement) On Haunching Area
- Laying FRP Mesh (45GSM) over the primed surface
- Application of Two coats of cementitious coat (Acrylic Polymer + cement) DFT -0.6 to 0.8mm
- Two coats of Titanium based, Water-proof cum Heat-proof, Anti-carbonation, Anti-fungal, Surface temperature reduces up to 15ºC, DFT – 1mm

NOTE: Final measurements and scope may vary slightly based on actual site conditions.

MIGNON MINDS LLP
42 & 43 Shop No. A6,
Praneeth Pranav Blooms,
Bowrampet, Hyderabad - 500043.

TERMS & CONDITIONS

- The working procedure and quotation are provided on a cost per square feet basis. The final bill will be based on the actual measurements of the area coated by Mignon minds.
- Any balance materials that are not used during the work will be taken back by Mignon minds and will not be provided to the customer.
- The customer should be aware of the color of the topcoat that they choose for their roof. Different colors have different cooling properties and may affect the temperature of the building. Mignon minds will not be liable for any difference in the cooling effect that may result from the customer's choice of color.
- Once the quoted price is approved, negotiation after completion of job cannot be entertained.
- Warranty card will be issued only upon receiving full payment.
- In the event of rain during the application process, where the coated material is washed away before they are cured, the company will bear the full cost of replacing the coating and will not charge the customers any extra fees.
- Power & Water supply shall be provided by the customer.
- Additional work rather than the quoted area will cost extra.

IMPORTANT WARRANTY NORMS

- Puncturing of cured membrane due to sharp objects, movements of heavy articles, fixing of Antenna or other structures on the terrace, any physical damage or abuse to the coated floor will not be considered for warranty claim.
- However, in case of any physical damage made by the customer during the warranty period, patchworks can be done to repair the damages upon extra cost depending on the type of repair.
- Warranty is applicable only when the entire terrace along with parapet wall needs to be enveloped as recommended.
- Only the surface immediately underneath the terrace or the top floor of the building, as the case may be, shall be covered under warranty. The warranty shall not cover the areas where the water seeps from surfaces that are NOT coated.
- The Warranty shall be for a period of either 5/10/15 years on terrace waterproofing, where any claim arises during the warranty period, the period will not start afresh after settlement of the claim.
- In case of coatings applied with manually mixed pigments, the warranty shall be provided only for the performance of the chemical and not for the pigment, hence discoloration / fading off of the color cannot be claimed under warranty.

+91 70326 73399

care@mignonminds.com

www.mignonminds.com